

**FEDERAL AVIATION ADMINISTRATION
FLIGHT STANDARDS SERVICE
TAKEOFF MINIMUMS AND OBSTACLE DEPARTURE PROCEDURES (ODP)
TITLE 14 CFR PART 97.37**

Bearings, headings, courses, tracks and radials are magnetic. Elevations and altitudes are in feet, MSL. Altitudes are minimum altitudes unless otherwise indicated.
Ceilings are in feet above airport elevation. Distances are in nautical miles. Visibilities are in statute miles or feet RVR unless otherwise indicated.

<u>AIRPORT</u>	<u>AIRPORT ID</u>	<u>CITY</u>	<u>STATE</u>	<u>AMDT NO</u>	<u>ACTUAL EFFECTIVE DATE</u>
HARRISON COUNTY	8G6	CADIZ	OH	4	

TAKEOFF MINIMUMS:

RWY 31: STANDARD.

RWY 13: 300 - 1 7/8 OR STANDARD WITH MINIMUM CLIMB OF 274 FT PER NM TO 1400.

TEXTUAL DEPARTURE PROCEDURES:

VISUAL CLIMB OVER AIRPORT:

TAKEOFF OBSTACLE NOTES:

NOTE: RWY 13: TREE, VEGETATION BEGINNING 31 FT FROM DER, 98 FT LEFT OF CENTERLINE, UP TO 1133 FT MSL.

BUILDING, TREE BEGINNING 55 FT FROM DER, 163 FT RIGHT OF CENTERLINE, UP TO 17 FT AGL/1127 FT MSL.

POLE, TREE BEGINNING 190 FT FROM DER, 114 FT LEFT OF CENTERLINE, UP TO 39 FT AGL/1148 FT MSL.

TREES BEGINNING 225 FT FROM DER, 154 FT RIGHT OF CENTERLINE, UP TO 1132 FT MSL.

TREE, POLE BEGINNING 407 FT FROM DER, 82 FT LEFT OF CENTERLINE, UP TO 1175 FT MSL.

TREE 656 FT FROM DER, 449 FT RIGHT OF CENTERLINE, 1137 FT MSL.

TREE 697 FT FROM DER, 281 FT RIGHT OF CENTERLINE, 1139 FT MSL.

TREE 722 FT FROM DER, 647 FT RIGHT OF CENTERLINE, 1144 FT MSL.

TREE 811 FT FROM DER, 450 FT RIGHT OF CENTERLINE, 1156 FT MSL.

TREES BEGINNING 858 FT FROM DER, 179 FT RIGHT OF CENTERLINE, UP TO 1158 FT MSL.

TREES BEGINNING 927 FT FROM DER, 58 FT RIGHT OF CENTERLINE, UP TO 1169 FT MSL.

TREE, TERRAIN, POLE, FENCE BEGINNING 1068 FT FROM DER, 44 FT RIGHT OF CENTERLINE, UP TO 1199 FT MSL.

TREE 1530 FT FROM DER, 151 FT LEFT OF CENTERLINE, 1195 FT MSL.

TREES BEGINNING 1620 FT FROM DER, 221 FT LEFT OF CENTERLINE, UP TO 1204 FT MSL.

TREES BEGINNING 1727 FT FROM DER, 4 FT LEFT OF CENTERLINE, UP TO 1215 FT MSL.

TERRAIN, TREE BEGINNING 1927 FT FROM DER, 22 FT RIGHT OF CENTERLINE, UP TO 1208 FT MSL.

TREES BEGINNING 2703 FT FROM DER, 87 FT LEFT OF CENTERLINE, UP TO 1220 FT MSL.

TREE, TERRAIN BEGINNING 2811 FT FROM DER, 228 FT RIGHT OF CENTERLINE, UP TO 1224 FT MSL.

TREE, TERRAIN BEGINNING 2944 FT FROM DER, 68 FT RIGHT OF CENTERLINE, UP TO 1230 FT MSL.

TREE 3047 FT FROM DER, 126 FT LEFT OF CENTERLINE, 1222 FT MSL.

TREE, TERRAIN BEGINNING 3080 FT FROM DER, 43 FT RIGHT OF CENTERLINE, UP TO 1232 FT MSL.

TREES BEGINNING 3277 FT FROM DER, 401 FT RIGHT OF CENTERLINE, UP TO 1233 FT MSL.

TREES BEGINNING 3399 FT FROM DER, 104 FT RIGHT OF CENTERLINE, UP TO 1234 FT MSL.

TREE 5966 FT FROM DER, 2009 FT RIGHT OF CENTERLINE, 1273 FT MSL.

TREE 1 NM FROM DER, 2037 FT RIGHT OF CENTERLINE, 1309 FT MSL.

TREES BEGINNING 1 NM FROM DER, 1544 FT RIGHT OF CENTERLINE, UP TO 1325 FT MSL.

TREE 1.3 NM FROM DER, 428 FT LEFT OF CENTERLINE, 1312 FT MSL.

TREES BEGINNING 1.3 NM FROM DER, 343 FT LEFT OF CENTERLINE, UP TO 1329 FT MSL.

TREES BEGINNING 1.4 NM FROM DER, 1568 FT LEFT OF CENTERLINE, UP TO 1339 FT MSL.

TREE 1.4 NM FROM DER, 1705 FT LEFT OF CENTERLINE, 1340 FT MSL.

TREES BEGINNING 1.5 NM FROM DER, 1653 FT LEFT OF CENTERLINE, UP TO 1350 FT MSL.

TREES BEGINNING 1.5 NM FROM DER, 1592 FT LEFT OF CENTERLINE, UP TO 1350 FT MSL.

NOTE: RWY 31: TERRAIN 40 FT FROM DER, 175 FT RIGHT OF CENTERLINE, 1198 FT MSL.

TERRAIN 71 FT FROM DER, 374 FT LEFT OF CENTERLINE, 1188 FT MSL.

TERRAIN 89 FT FROM DER, 287 FT RIGHT OF CENTERLINE, 1219 FT MSL.

TERRAIN 99 FT FROM DER, 195 FT LEFT OF CENTERLINE, 1194 FT MSL.

TREES AND FENCE BEGINNING 136 FT FROM DER, 5 FT RIGHT OF CENTERLINE, UP TO 1229 FT MSL.

TERRAIN 196 FT FROM DER, 494 FT LEFT OF CENTERLINE, 1213 FT MSL.

TREES BEGINNING 204 FT FROM DER, 200 FT LEFT OF CENTERLINE, UP TO 1214 FT MSL.

FENCE BEGINNING 341 FT FROM DER, 97 FT LEFT OF CENTERLINE, UP TO 3 FT AGL/1218 FT MSL.

TREES AND FENCE BEGINNING 403 FT FROM DER, 1 FT RIGHT OF CENTERLINE, UP TO 1235 FT MSL.

FENCE BEGINNING 485 FT FROM DER, 100 FT LEFT OF CENTERLINE, UP TO 4 FT AGL/1219 FT MSL.

FENCE BEGINNING 802 FT FROM DER, 109 FT LEFT OF CENTERLINE, UP TO 4 FT AGL/1224 FT MSL.

QUALITY
19
CHECKED

AIRPORT	AIRPORT ID	CITY	STATE	AMDT NO	EFFECTIVE DATE
HARRISON COUNTY	8G6	CADIZ	OH	4	

FENCE AND VEGETATION BEGINNING 964 FT FROM DER, 41 FT LEFT OF CENTERLINE, UP TO 4 FT AGL/1226 FT MSL.

TREES AND FENCE BEGINNING 991 FT FROM DER, 88 FT LEFT OF CENTERLINE, UP TO 1229 FT MSL.

CONTROLLING OBSTACLES:

RWY 13: 1325 FT MSL TREE 401311.42N/0805934.31W (CLIMB GRADIENT, CLIMB-TO-ALTITUDE),
1350 FT MSL TREE 401326.92N/0805835.15W (CEILING),
1350 FT MSL TREE 401324.92N/0805834.46W (VISIBILITY).

REMARKS:

FLIGHT INSPECTED BY

OFFICE

DATE

DEVELOPED BY

OFFICE

DATE

DONALD LANIER (SCOTT LINDHOLM)

AJV-A431

01/29/2020

APPROVED BY

OFFICE

DATE

TITLE

GEORGE DAVIS

AJV-A430

MANAGER

REQUIRED EFFECTIVE DATE:

ROUTINE

COORDINATED WITH:

A4A ☐ **ALPA** ☒ **AOPA** ☒ **APA** ☐ **HAI** ☐ **NBAA** ☒ **OTHER:** CLE APP CON, AMGR

CHANGES - REASONS:

1. CHANGED RWY 13 TAKEOFF MINIMUMS FROM "300 - 1" TO "300 - 1 7/8 OR STANDARD WITH MINIMUM CLIMB OF 274 FT PER NM TO 1400". - NEW EVALUATION.
2. CHANGED RWY 31 TAKEOFF MINIMUMS FROM "300-1" TO "STANDARD" - NEW EVALUATION.
3. UPDATED TAKEOFF OBSTACLE NOTES. - NEW SURVEY.
4. UPDATED CONTROLLING OBSTACLES. - NEW SURVEY.

