

U.S. DEPARTMENT OF TRANSPORTATION – FEDERAL AVIATION ADMINISTRATION
TAKEOFF MINIMUMS AND OBSTACLE DEPARTURE PROCEDURES (ODP)

Bearings, headings, courses, tracks and radials are magnetic. Elevation and altitudes are in feet MSL. Altitudes are minimum altitudes unless otherwise indicated.
Ceilings are in feet above airport elevation. Distances are in nautical miles. Visibilities are in statute miles or feet RVR unless otherwise indicated.

City, State	Airport	Effective Date	Amdt. No.
PETERSBURG, WV	GRANT COUNTY	19 SEPTEMBER 2013	1

TAKEOFF MINIMUMS:

RWY 13, 31: 2400 – 3 FOR CLIMB IN VISUAL CONDITION.

TEXTUAL DEPARTURE PROCEDURES:

FOR CLIMB IN VISUAL CONDITIONS, CROSS GRANT COUNTY AIRPORT NORTHEAST BOUND AT OR ABOVE 3200, THEN CLIMB TO 5000 ON ESL R-214 DIRECT ESL VOR/DME. WHEN EXECUTING VCOA, NOTIFY ATC PRIOR TO DEPARTURE.

TAKEOFF OBSTACLE NOTES:

RWY 13: TREES 517 FT FROM DER, 609 FT LEFT OF CENTERLINE, UP TO 70 FT AGL / 1029 FT MSL. TREES BEGINNING 3042 FT FROM DER, 1304 FT RIGHT OF CENTERLINE, UP TO 100 FT AGL / 1099 FT MSL.

RWY 31: TREES 182 FT FROM DER, 546 FT RIGHT OF CENTERLINE, UP TO 100 FT AGL / 1099 FT MSL. VEHICLES ON ROAD 1651 FT FROM DER, 927 FT RIGHT OF CENTERLINE, UP TO 15 FT AGL / 1054 FT MSL. BUILDING 2553 FT FROM DER, 414 FT RIGHT OF CENTERLINE, 30 FT AGL / 1029 FT MSL. TREES BEGINNING 3642 FT FROM DER, 651 FT LEFT OF CENTERLINE, UP TO 100 FT AGL / 1139 FT MSL.

CONTROLLING OBSTACLES:

VCOA: 2930 FT MSL AAO 390216.71N/0790522.78W.

U.S. DEPARTMENT OF TRANSPORTATION – FEDERAL AVIATION ADMINISTRATION
TAKEOFF MINIMUMS AND OBSTACLE DEPARTURE PROCEDURES (ODP)

Bearings, headings, courses, tracks and radials are magnetic. Elevation and altitudes are in feet MSL. Altitudes are minimum altitudes unless otherwise indicated.
Ceilings are in feet above airport elevation. Distances are in nautical miles. Visibilities are in statute miles or feet RVR unless otherwise indicated.

City, State	Airport	Effective Date	Amdt. No.
PETERSBURG, WV	GRANT COUNTY	19 SEPTEMBER 2013	1

REMARKS:

FLIGHT INSPECTED BY:

for Dustin Welsh *[Signature]* 4/10/13

REQUIRED EFFECTIVE DATE:

ROUTINE

DEVELOPED BY:

for DON SMITH *[Signature]* AJV-352 12/06/2012
(DUSTIN R. DAVIDSON)

APPROVED BY:

for SUE CRUMB *[Signature]* AJV-352 JUL 29 2013

COORDINATED WITH:

AOPA, ALPA, NBAA, ZDC, ARPT MGR

CHANGES:

1. INCREASED TAKEOFF MINIMUMS CEILING FROM 1500 TO 2400.
2. ADDED TAKEOFF OBSTACLE NOTES.
3. UPDATED TEXTUAL DEPARTURE PROCEDURE.

REASONS:

1. NEW CONTROLLING OBSTACLE.
2. NEW LOW CLOSE-IN OBSTACLES
3. IAW 8260.3B CHG 19, VOL 4, PARA 4.2.3.